

SUPERPAVE TESTING LABORATORIES



GENERAL:

The labs are constructed with large structural members and solid steel floors. The labs are designed to last 25-30 years. The labs include wood cabinets with stainless steel tops, an HVAC Unit, a 200-Amp load center, and all the needed receptacles for testing equipment.

Basic Sizes

65' x 10'

50' x 10'

35' x 10'





FEATURES

- 3/16" Solid Steel Floor
- Surface-Mounted Electrical for all receptacles and switches
- Wainscot Laminated Wallboard
- 200-Amp Load Center with Quick Connect
- Thermostatically Controlled HVAC Unit
- Wooden Cabinets with Stainless Steel Tops
- Office with wrap around desk capable of housing computer & printer
- Fluorescent Lighting
- R-19 Insulation in Walls and Ceilings

